BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/01/2015-16, Date:04.01.2016 **Indent No.20425**

SCHEDULE-B

NAME OF WORK: Improvements to roads and drains at vinayaka layout, Medarahalli near RR college in W.no.12 Shetty halli Sub division

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **R SHIVARAM**		
				In Figures (Rs.)	In Words (Rs.)	Cont. AMOUNT
1	2	3	4	5	6	7
1	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specfication & as per direction of Engineer-in-charge	Cum	857.84	109.0	Rupees One Hundred Nine Only	93504.56
2	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 7.5 cms thick complete as per specfication & as per direction of Engineer-in-charge	Cum	1126.8	624.0	Rupees Six Hundred Twenty Four Only	703123.20
3	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specifications including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel/vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening/binding Materials to fill up the interstices of coarse aggregates, watering and compacting to the required density Complete as per Specification. A. By manual means. MORTH Specification No. 404. Type A 13.2mm for grading II. complete as per specfication & as per direction of Engineer-in-charge	Cum	275.55	1647.0	Rupees One Thousand Six Hundred Forty Seven Only	453830.85

Signature of the Contractor

Executive Engineer

4	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specifications including spreading in uniform thickness, hand packing, rolling with 3 wheeled steel/vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening/binding Materials to fill up the interstices of coarse aggregates, watering and compacting to the required density Complete as per Specification. A. By manual means. MORTH Specification No. 404. Type B 11.2mm for grading III. complete as per specfication & as per direction of Engineer-in-charge	Cum	137.78	1756.0	Rupees One Thousand Seven Hundred Fifty Six Only	241932.90
5	Carriage of mixed materials 10 Kms, For items of Sl.no 1.c) rs. 5.26 per cum/km. complete as per specfication & as per direction of Engineer-in-charge	Cum	413.33	74.0	Rupees Seventy Four Only	30586.05
6	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 10 Km a)Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b)Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c)Add loading and unloading complete as per specfication & as per direction of Engineer-in-charge	Cum	857.84	69.0	Rupees Sixty Nine Only	59190.96
					Total	1584377.73
					Percentage	-5.86%

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,